



**Notes Room 173:**

1. Construct new freestanding worktable and shelf to match existing worktable and build a new shelf for worktable that is remaining. (See elevaton "A" on Drawing C-2)
2. Move center-island shelving unit to north wall as show on plan.
3. Reuse or purchase shelves to increase storage space on north wall shelving unit by reducing shelf height spacing
4. Install 2-way switch on wall of room 173 between Rooms 173 & 171.

**Corridor:**

5. New ceiling hung sign in hallway outside new entry to identify LTS offices. sign provided by others.
6. Provide two new directional spot lights on either side of new sign.

**LEHIGH UNIVERSITY**  
**EWFM - Computer Shop & Office**

**CONSTRUCTION PLAN**

Scale: 1/4" = 1'-0"

Revised: July 31, 2007

Contact: Mary Jo Brown x 8-5027 / mjb@lehigh.edu



C-1