

Demolition and/or Removal

Room 173:

- 1. Disconnect electrical strips on both worktable and shelves.
- 2. Remove shelf from above the other existing worktable. (only after new shelf is ready to be installed.)
- 3. Remove and discard old worktable and associated overhead shelf. (only after new worktable and shelf are ready to be installed. See Elevation "A" on Drawing C-2)
- 4. Remove and discard 4 or 5 metal shelving units located along back wall. Keep better one for reuse.

LEGEND Demolition Existing to remain To be moved

LEHIGH UNIVERSITY EWFM - Computer Shop & Office

